

**SUBJECT:** Purchase of Custom Hazmat Truck body from TriVan Truck Body in the amount of \$186,912.72

**AGENDA OF:** August 20, 2024

**ASSEMBLY ACTION:**

Approved under the consent agenda - EMW

**AGENDA ACTION REQUESTED:** Present to the Assembly for consideration.

Route To:	Signature
Originator	X Rustin Krafft <small>Signed by: Rustin Krafft 8/8/2024</small>
DES Director	X Ken Barkley <small>Recoverable Signature Signed by: Ken Barkley</small>
Purchasing Director	X Rustin Krafft <small>Signed by: Rustin Krafft 8/8/2024</small>
Finance Director	X Cheyenne Heindel <small>Signed by: Cheyenne Heindel 8/9/2024</small>
Borough Attorney	X Nicholas Spiropoulos <small>Signed by: Nicholas Spiropoulos 8/9/2024</small>
Borough Manager	X Michael Brown <small>Signed by: Mike Brown 8/9/2024</small>
Borough Clerk	X Lonnie Mckechnie <small>Recoverable Signature Signed by: Lonnie Mckechnie</small>

**ATTACHMENT (S):** Quote for Hazmat Van(16pp)  
Fiscal Note (1p)

**SUMMARY STATEMENT:** The Department of Emergency Services has identified a need to acquire a new HAZMAT response truck body. This vehicle will replace a recently retired response van.

Due to the specialized nature of the purchase and the need to customize it to the MSB truck body, the traditional bid and proposal process would not be appropriate method of sourcing. Instead, 3 previous and reputable vendors were contacted to provide pricing and delivery. Based on those conversations, TriVan Truck Body was selected based on their ability to deliver an acceptable design along with pricing and delivery.

Delivery is anticipated no later than 1/31/2026.

**RECOMMENDATION OF ADMINISTRATION:** Approve the legislation as presented.

**MATANUSKA-SUSITNA BOROUGH**

**FISCAL NOTE**

Agenda Date: August 20, 2024

**SUBJECT: Purchase of Custom Hazmat Truck body from TriVan Truck Body in the amount of \$186,912.72**

FISCAL ACTION (TO BE COMPLETED BY FINANCE)	FISCAL IMPACT <b>YES</b> NO
AMOUNT REQUESTED \$186,912.72	FUNDING SOURCE Ambulance & EMS Cap Projects
FROM ACCOUNT # 425.000.000 4XX.XXX	PROJECT# 45167
TO ACCOUNT:	PROJECT #
VERIFIED BY:  X Merissa Carrell Signed by: Merissa Carrell	

**EXPENDITURES/REVENUES:** (Thousands of Dollars)

OPERATING	FY2024	FY2025	FY2026	FY2027	FY2028	FY2029
Personnel Services						
Travel						
Contractual						
Supplies						
Equipment						
Land/Structures						
Grants, Claims						
Miscellaneous						
<b>TOTAL OPERATING</b>						

CAPITAL		186.9				
---------	--	-------	--	--	--	--

REVENUE						
---------	--	--	--	--	--	--

**FUNDING:** (Thousands of Dollars)

General Fund						
State/Federal Funds						
Other		186.9				
<b>TOTAL</b>		186.9				

**POSITIONS:**

Full-Time						
Part-Time						
Temporary						

**ANALYSIS: (Attach a separate page if necessary)**

APPROVED BY:	8 / 9 / 2 0 2 4
X Cheyenne Heindel	

Signed by: Cheyenne Heindel

AM No. 24-095  
Ordinance Serial No. 24-\_\_\_\_  
Resolution Serial No. 24-\_\_\_\_



**TriVan Truck Body**

1385 West Smith Road  
Ferndale, WA 98248

Ph (360) 380-0773 www.trivan.com  
Fax (360) 312-1398

# Estimate

Date	Estimate #
7/23/2024	10258

Name / Address
Matanuska-Susitna Borough Brent Davenport 680 N. Seward Meridian Parkway Wasilla AK 99654

Ship To
FOB Ferndale WA

P.O. No.	Terms	Due Date	Rep	Account #	FOB	Project
TBD	Due on receipt	8/21/2025	Ryan		Ferndale WA	

Item	Description
QUOTATION	<p>QUOTATION:            Custom rescue dive team truck body (chassis to be provided by Mat-Su Borough)            End-user: Matanuska-Susitna Borough Rescue Dive Team            This quotation expires September 30, 2024            Terms: 35% deposit due at time of order, with full balance due upon completion, prior to pickup.            Current build time is 500 days after receipt of your chassis.            FOB Ferndale WA.</p> <p>16'L(OD) TriVan Van Body</p>
DESCRIPTION	<p>GENERAL DESCRIPTION:            Custom 16' van body to be installed on a new, Mat-Su supplied 2023 Chevy 5500 Crew Cab diesel chassis. TriVan to install the body &amp; upfit the vehicle with a Class V hitch receiver. The truck body interior includes bench-seating, personal storage cubicles, gear storage cabinetry. SnapLock body construction with formed aluminum doors. The exterior roadside of the body to have exterior access aluminum vented storage compartments. The van body will be insulated in R21 (3") spray-foam insulation (walls, ceiling, under floor). Interior lining to be white aluminum sheeting. Includes 48" length sloped over-cab extension. 110V power supplied by a 3000W Xantrex inverter with house battery system. A 110V/20A shore power receptacle will recharge the battery bank thru charger system. No air conditioning. Includes electric heater. The van body interior &amp; exterior will include 12V Maxxima LED interior &amp; Whelen emergency LED exterior lighting. Roadside interior of body to include (2) banks of adjustable aluminum shelves, a 73" length work counter with 2 drawers. The curbside interior of the body to include a 4 person bench-seat (no seat belts) and wall-mounted SCBA storage brackets (4) plus (4) overhead cubbies and a double-door large aluminum floor to ceiling storage closet with mesh doors &amp; lower drawers. Rear doors are swing out doors (rear door configuration to allow doors to be fully opened and not stick out past the edges of the body) A curbside forward entry door (with stepwell) also provided. Flooring of body to be aluminum diamond plate floor including (2) front corner drain holes (for washout/hoseout) Standard 040 aluminum roof. This proposal includes mounting &amp; installation of the van body to customer-supplied chassis. Exterior lighting to be all-LED, all-Whelen, and will include (6) scene lights, and (8) M9-series split red/blue lights. TriVan to install body. Customer to arrange pickup from Ferndale WA. Full AutoCad presentation drawings will be provided to Mat-Su Borough for approval prior to manufacturing the body.</p>

<b>Subtotal</b>
<b>Sales Tax (0.0%)</b>
<b>Total</b>



**TriVan Truck Body**

1385 West Smith Road  
Ferndale, WA 98248

Ph (360) 380-0773 www.trivan.com  
Fax (360) 312-1398

# Estimate

Date	Estimate #
7/23/2024	10258

Name / Address
Matanuska-Susitna Borough Brent Davenport 680 N. Seward Meridian Parkway Wasilla AK 99654

Ship To
FOB Ferndale WA

P.O. No.	Terms	Due Date	Rep	Account #	FOB	Project
TBD	Due on receipt	8/21/2025	Ryan		Ferndale WA	
Item	Description					
CHASSIS INFO	CHASSIS INFORMATION (CUSTOMER PROVIDED) 2023 Chevy 5500 Crew Cab 4x4, 120" cab-axle ~ GVWR: 19,500 lb Payload Plus Upgrade Package ~ dual rear wheels ~ 4-door crew cab ~ Mat-Su to arrange to have this chassis drop-shipped to TriVan Truck Body					
DIMENSIONS	DIMENSIONS: Length: 16'L(od) plus 4' over-cab extension Width: 8'W(od) Height: 7'H(id)					
DESIGN DRA...	DESIGN DRAWINGS: AutoCad design drawings shall be provided for Mat-Su approval prior to manufacture.					
SUBFRAME 2x2	SUBFRAME & WHEEL-WELLS: Subframe constructed of 2"x2" tubular steel cross-members 16" on center with longsills to suit supplied chassis. Includes wheel wells for low floor height. Includes custom clearance for tire chains.					
BUMPER-STEP	STEP BUMPER + FOLDOUT STEP + HITCH + ANCHOR POINTS: 10"D galvanized steel Grip Strut step bumper installed at rear. Includes tapered 45 degree corners ~ Bumper to incorporate a Class V receiver hitch that is reinforced to chassis frame rails. ~ Bumper is primed & painted black  FOLDOUT STEP: Supply & Install (1) 48"W hinged foldout step off rear bumper, same Grip Strut material as main bumper ~ foldout step to include a stainless) spring-loaded barrel bolt (to stow bumper securely in storage position)					
HITCH	CLASS V HITCH: Class V hitch receiver installed & reinforced to chassis frame rails. ~ Installation includes (1) 7-way ROUND COMMERCIAL trailer plug					
WALLS	WALL CONSTRUCTION: SnapLock wall construction. Note: all exterior doors to be FORMED style.					

<b>Subtotal</b>
<b>Sales Tax (0.0%)</b>
<b>Total</b>



**TriVan Truck Body**

1385 West Smith Road  
Ferndale, WA 98248

Ph (360) 380-0773 www.trivan.com  
Fax (360) 312-1398

# Estimate

Date	Estimate #
7/23/2024	10258

Name / Address
Matanuska-Susitna Borough Brent Davenport 680 N. Seward Meridian Parkway Wasilla AK 99654

Ship To
FOB Ferndale WA

P.O. No.	Terms	Due Date	Rep	Account #	FOB	Project
TBD	Due on receipt	8/21/2025	Ryan		Ferndale WA	
Item	Description					
SKIRTING	SKIRTING: Snap-Lock panel perimeter wall skirting flush to bottom of cab. ~ rounded wheel cutouts with rubber fender crowns ~ cutouts are large enough to allow tire-chain clearance.					
KICKOVER-4'	KICKOVER 4'L sloped kickover installed at front of body, finished & lined per rest of van body interior, ~ Insulated 3" urethane foam, lined in Kemlite over plywood. ~ includes an exterior wraparound continuous drip rail system ~ includes diamond plate protective wear plate on interior (near bottle storage rack)					
ROOF	ROOF: Standard .040" single piece aluminum roof, cross-bows 24" on center, with standard TriVan crown.					
WINDOWS	WINDOWS: No windows.					
ALUM DIAMO...	FLOORING Flooring of van body interior to be 3/16" aluminum diamond plate flooring. No bedliner.					
INSULATION	INSULATION 3" urethane spray-foam insulation (R21) applied to walls, ceiling, under floor and entry doors and kickover.					
LINING	WALL LINING: Walls & ceiling lined in white, aluminum sheeting on full interior, including 4" retainer lip installed on edge of kickover.					
FINISH TRIM &...	TRIMOUT Extra labor for interior lining on interior of specialty units (including extra trim work, capping, caulking, special cutouts)					
DOORS	REAR DOORS: (2) 25" formed aluminum double doors at rear (approx 50"W clear opening) with TriMark paddle handles, stainless piano hinges and cast aluminum holdbacks. Doors to be insulated and lined to match the body interior.					

<b>Subtotal</b>
<b>Sales Tax (0.0%)</b>
<b>Total</b>



**TriVan Truck Body**

1385 West Smith Road  
Ferndale, WA 98248

Ph (360) 380-0773 www.trivan.com  
Fax (360) 312-1398

# Estimate

Date	Estimate #
7/23/2024	10258

Name / Address
Matanuska-Susitna Borough Brent Davenport 680 N. Seward Meridian Parkway Wasilla AK 99654

Ship To
FOB Ferndale WA

P.O. No.	Terms	Due Date	Rep	Account #	FOB	Project
TBD	Due on receipt	8/21/2025	Ryan		Ferndale WA	

Item	Description
STEPWELL (2)	CURBSIDE DOOR: (1) 30"W x 84" Aluminum FORMED curbside door entry door, located at very front, with (2) recessed aluminum diamondplate inside steps. Includes TriMark paddle handle and cast aluminum holdback. Door is insulated & lined per rest of body interior.
INTERIOR FINI...	All-aluminum construction, painted white.  ROADSIDE INTERIOR FURNISHINGS: ~ Supply & install the following: ~ (3) aluminum J-style hanger hooks on front wall, as space allows ~ (2) 54"W x 22"D aluminum shelving units, each with (3) adjustable shelves ~ (1) 72"W x 22"D Formica work counter (between the 2 shelving units) with (2) lower drawers  CURBSIDE INTERIOR FURNISHINGS: Supply & Install the following: ~ (1) +/- 81"W x 22"D x 27"H cushioned high-density foam bench-seat cushion over top of storage box bench-seat. no back-rest. Cushion is to be wrapped in black marine-grade vinyl and bench ~ (1) +/- 32"W x 22"D x 84"H Floor-to-ceiling double-door cabinet at very rear of body (right-hand-side upon entry at rear doors); ~ Upper +/- 5'H of cabinet to be solid alum doors w/ adjustable shelves. ~ Lower +/- 2'H of cabinet has (2) 250lb extra tall lower drawers, with travel-safe latches (non-locking is ok) and rubber matt inserts ~ (1) 4-space x 12"H overhead cubby compartment cabinet (open-faced, with front retainer lip) directly above bench-seat (for personal gear)
SEATBELTS	SEATBELTS: deleted.
FUEL FILLER	FUEL FILLER & DEF FILLER: Supply & install recessed fuel filler pod on driver side of vehicle wheelhouse skirt panel area, with standard hose assembly, to suit chassis fuel tank and DEF tank as necessary.

<b>Subtotal</b>
<b>Sales Tax (0.0%)</b>
<b>Total</b>



**TriVan Truck Body**

1385 West Smith Road  
 Ferndale, WA 98248

Ph (360) 380-0773 www.trivan.com  
 Fax (360) 312-1398

# Estimate

Date	Estimate #
7/23/2024	10258

Name / Address
Matanuska-Susitna Borough Brent Davenport 680 N. Seward Meridian Parkway Wasilla AK 99654

Ship To
FOB Ferndale WA

P.O. No.	Terms	Due Date	Rep	Account #	FOB	Project
TBD	Due on receipt	8/21/2025	Ryan		Ferndale WA	

Item	Description
EXTERIOR CO...	<p><b>EXTERIOR STORAGE COMPARTMENTS:</b>            ~ Supply &amp; install 1/8" aluminum exterior storage compartments, complete with FORMED aluminum doors with TriMark paddle handles.            ~ These compartments are to be "thru-the-floor" style, extending from bottom of skirt, up through the floor, per drawings            ~ Horizontal compartments will be located above the rear axle, both sides of truck body.</p> <p><b>DOOR HARDWARE:</b>            ~ Door hardware to be stainless steel recessed paddle handles with 2-point rotary latches &amp; adjustable stryker bolts            ~ All doors hinged on stainless steel piano hinges.</p> <p><b>ROADSIDE COMPARTMENTS, starting from very front:</b>            ~ RSV1 - (1) tall vertical compartment, single door, approx 24"W x 38"H, very front (3 adj shelves)            ~ RSV2 - (1) vertical compartment, single door, approx 22-3/4"W x 38"H, ahead of rear axle (2 adj shelves)            ~ RSH - (1) horizontal, double-door compartment, approx 61"W x 14"H, over rear axle. (no shelves)            ~ RSV3 - (1) vertical compartment, single door, approx 35"W x 38"H, very rear. (2 adj. shelves)            As space allows, Mat-Su has requested (1) additional roadside exterior compartment approx 24"W with shelves.</p> <p><b>CURBSIDE COMPARTMENTS ~ DELETED</b></p> <p><b>NOTE:</b>            ~ Horizontal compartment door to include detachable retainer cables (or chains) that allow the door to form either a flat work surface (when opened) or to lay flat against the side of the body (with cables detached) All vertical exterior compartment doors will include gas struts (to hold doors open and assist in door closure)</p>
12V ELECTRI...	<p><b>FMVSS ELECTRICAL</b>            To TriVan standard wiring specifications including:            ~ All wiring joints to be soldered and heat-shrunk with insulated tubing.            ~ LED Signal Lights: 4" round stop-tail-turn signals            ~ LED Reverse Lights: 4" round stop-tail-turn signals            ~ LED licence plate light and reflectors as necessary.</p>

<b>Subtotal</b>
<b>Sales Tax (0.0%)</b>
<b>Total</b>



**TriVan Truck Body**

1385 West Smith Road  
Ferndale, WA 98248

Ph (360) 380-0773 www.trivan.com  
Fax (360) 312-1398

# Estimate

Date	Estimate #
7/23/2024	10258

Name / Address
Matanuska-Susitna Borough Brent Davenport 680 N. Seward Meridian Parkway Wasilla AK 99654

Ship To
FOB Ferndale WA

P.O. No.	Terms	Due Date	Rep	Account #	FOB	Project
TBD	Due on receipt	8/21/2025	Ryan		Ferndale WA	

Item	Description
12V LIGHTING...	<p><b>INTERIOR 12V LED LIGHTING:</b> Supply &amp; install (8) Maxxima M84418-SW LED surface-mounted interior cargo lights, installed on ceiling, 2 parallel runs of (4) lights, end-to-end evenly spaced, switched @ rear door. All lights on one switch.</p> <p>COMPARTMENT 12V LIGHTING: deleted.</p>
RED/BLUE LE...	<p><b>EMERGENCY LIGHTING PACKAGE:</b></p> <p><b>RED/BLUE FLASHERS:</b> Supply &amp; install (6) Whelen M9J "M" series super linear red/blue LED flasher lights (each with M9FC chrome flange): ~ (2) on rear wall, (2) on curbside, (2) on roadside, plus (2) Whelen LINZ6 red/blue in chassis grille. ~ Includes (1) illuminated switch in cab to activate all at once. (see LIGHT CONTROLS)</p> <p><b>LED SCENE LIGHTS:</b> Supply &amp; install (6) Whelen M9LZC "M" series LED scene lights (each with M9FC chrome flange) ~ (2) on rear wall, (2) on curbside, (2) on roadside ~ Includes (1) illuminated switch in cab (see LIGHT CONTROLS)</p> <p><b>LIGHT CONTROLS:</b> Supply &amp; install (1) switch controller console in cab to control red/blue flashers &amp; scene lights</p> <p><b>TOMAR:</b> Siren/amplifier and controls in cab, installed, as on previous unit. Note: the Whelen lightbar (on top of cab roof) is not part of this quotation.</p>

<b>Subtotal</b>
<b>Sales Tax (0.0%)</b>
<b>Total</b>



**TriVan Truck Body**

1385 West Smith Road  
Ferndale, WA 98248

Ph (360) 380-0773 www.trivan.com  
Fax (360) 312-1398

# Estimate

Date	Estimate #
7/23/2024	10258

Name / Address
Matanuska-Susitna Borough Brent Davenport 680 N. Seward Meridian Parkway Wasilla AK 99654

Ship To
FOB Ferndale WA

P.O. No.	Terms	Due Date	Rep	Account #	FOB	Project
TBD	Due on receipt	8/21/2025	Ryan		Ferndale WA	
Item	Description					
INVERTER-30...	<p><b>INVERTER:</b> Supply &amp; Install (1) Xantrex 3000WPure Sinewave Inverter with Built-In Charger. To be hard-wired to (3) interior GFCI 15A duplex plugs and (1) exterior GFCI plug (curbside exterior) ~ Installation includes a control panel (suggested model 809-0910) installed at roadside desk area. ~ Installation also includes Fuse Block and fuse to suit. with automatic charge function to allow charging from vehicle alternator as well as from inverter.</p> <p><b>BATTERIES:</b> Includes installation of (2) Group 31 deep cycle batteries on slide out tray in bottom of driver side compartment second front front.</p>					
GRABHANDLE...	GRAB HANDLES: Supply & install (3) firetruck style grab handles, each with end-stanchions and rubber grip insert.					
PAINT	<p><b>PAINT:</b> Body exterior (excluding roof) painted Chevrolet white to match F-550 cab. Exterior compartment interiors left mill-finish aluminum.</p>					
UNDERCOATI...	<p><b>UNDERCOATING:</b> Underside of body to be fully undercoated, including bottom exterior undersides of all exterior bins.</p>					
MOUNTING	<p><b>MOUNTING:</b> Body to be mounted by TriVan on customer supplied chassis, includes TriVan mudflaps and anti-sway brackets.</p>					
FINISHING	<p><b>FINISHING:</b> Extruded aluminum drip rails installed above all exterior cabinet doors. 1 full wraparound continous drip rail on front of kickover, including 4' side arms for water run off diversion. 1 pair of TriVan mudflaps installed, including anti-sway brackets. Reflectors as necessary &amp; grab handles where required.</p>					
DELIVERY	<p><b>DELIVERY:</b> FOB TriVan Truck Body Ferndale WA (we are approximately a 3 hour drive from the Span Alaska Barge terminal)</p>					
	<p>THIS QUOTATION EXPIRES 9/30/2024 Build time is approx 500 days after receipt of chassis.</p>					

<b>Subtotal</b>	USD 186,912.72
<b>Sales Tax (0.0%)</b>	USD 0.00
<b>Total</b>	USD 186,912.72



# SOLICITATION REQUISITION FORM

**Purchasing Division**  
350 East Dahlia Avenue,  
Palmer, Alaska 99645-6488  
PHONE (907) 861-8601  
Purchasing@MatSuGov.us

**PROJECT TITLE:**

Replacement Rescue HAZMAT Team Apparatus

**REQUESTING PERSON/DIVISION/DEPARTMENT:**

Brent Davenport/ Emergency Services/ Rescue

**REVISED FORM/VERSION:**

No

**STAKEHOLDER DEPT.:**

Emergency Services

**ASSEMBLY DISTRICT #:**

Areawide

**DATE NEEDED BY:**

07/24/2024

**PURCHASE TYPE:**  CONSTRUCTION |  PROFESSIONAL SERVICE |  SERVICE |  SUPPLIES

Scope of Work/Scope of Services, specifications, supplemental general conditions, drawings, plans and/or all other documents are required to issue the solicitation and must be provided with this request and funding verification document.

Item No.	Description	Qty. Requested	Unit	Est. Unit Price	Est. Line Total / Est. Contract Amount
1	Construction and installation of 16' customized aluminum insulated HAZMAT van body on chassis supplied by MSB.	1		186,912.72	186,912.72
				ESTIMATED TOTAL ALL	
				<b>DO NOT EXCEED</b>	200,000.00

**ACCOUNTING****FUNDING TYPE(S):**  MSB |  STATE |  FEDERAL |  DHS&EM/FEMA |  NOT CURRENTLY FUNDED/PENDING

\* If the project is subject to state or federal grant funding that requires special procurement provisions or terms, provide a copy of the grant.

Account Number	Project	Source	Sub-Project	Amount	Project Exp. Date
425.000.000.464.451	45167	1800	1860	186,912.72	06/30/2026

**APPROVAL / CERTIFYING**

<b>REQUESTER NAME &amp; TITLE (PRINT NAME &amp; TITLE)</b> Brian Davis, Fire Deputy Director	<b>REQUESTER'S SIGNATURE</b> Brian C Davis	<b>DATE</b> Digitally signed by Brian C Davis Date: 2024.07.24 09:45:21 -08'00'
<b>DEPARTMENT DIRECTOR NAME &amp; TITLE (PRINT NAME &amp; TITLE)</b> Ken Barkley, Director Emergency Services	<b>DEPARTMENT DIRECTOR'S SIGNATURE</b> Ken Barkley	<b>DATE</b> Digitally signed by Ken Barkley Date: 2024.07.24 09:52:22 -08'00'
<b>CERTIFICATION:</b> I certify that the facts herein and on supporting documents are correct, that this voucher constitutes a legal charge against funds and appropriations cited, that sufficient funds are encumbered to pay this obligation, or that there is a sufficient unencumbered balance in the appropriation cited to cover this obligation.		
<b>CERTIFYING OFFICER NAME &amp; TITLE (PRINT NAME &amp; TITLE)</b> Merissa Carrell, Assistant Comptroller	<b>CERTIFYING OFFICER'S SIGNATURE</b> Merissa Carrell	<b>DATE</b> Digitally signed by Merissa Carrell Date: 2024.07.24 10:29:33 -08'00'



**TriVan Truck Body**

1385 West Smith Road  
Ferndale, WA 98248

Ph (360) 380-0773 www.trivan.com  
Fax (360) 312-1398

# Estimate

Date	Estimate #
7/23/2024	10258

Name / Address
Matanuska-Susitna Borough Brent Davenport 680 N. Seward Meridian Parkway Wasilla AK 99654

Ship To
FOB Ferndale WA

P.O. No.	Terms	Due Date	Rep	Account #	FOB	Project
TBD	Due on receipt	8/21/2025	Ryan		Ferndale WA	

Item	Description
QUOTATION	<p>QUOTATION:            Custom rescue dive team truck body (chassis to be provided by Mat-Su Borough)            End-user: Matanuska-Susitna Borough Rescue Dive Team            This quotation expires September 30, 2024            Terms: 35% deposit due at time of order, with full balance due upon completion, prior to pickup.            Current build time is 500 days after receipt of your chassis.            FOB Ferndale WA.</p> <p>16'L(OD) TriVan Van Body</p>
DESCRIPTION	<p>GENERAL DESCRIPTION:            Custom 16' van body to be installed on a new, Mat-Su supplied 2023 Chevy 5500 Crew Cab diesel chassis. TriVan to install the body &amp; upfit the vehicle with a Class V hitch receiver. The truck body interior includes bench-seating, personal storage cubicles, gear storage cabinetry. SnapLock body construction with formed aluminum doors. The exterior roadside of the body to have exterior access aluminum vented storage compartments. The van body will be insulated in R21 (3") spray-foam insulation (walls, ceiling, under floor). Interior lining to be white aluminum sheeting. Includes 48" length sloped over-cab extension. 110V power supplied by a 3000W Xantrex inverter with house battery system. A 110V/20A shore power receptacle will recharge the battery bank thru charger system. No air conditioning. Includes electric heater. The van body interior &amp; exterior will include 12V Maxxima LED interior &amp; Whelen emergency LED exterior lighting. Roadside interior of body to include (2) banks of adjustable aluminum shelves, a 73" length work counter with 2 drawers. The curbside interior of the body to include a 4 person bench-seat (no seat belts) and wall-mounted SCBA storage brackets (4) plus (4) overhead cubbies and a double-door large aluminum floor to ceiling storage closet with mesh doors &amp; lower drawers. Rear doors are swing out doors (rear door configuration to allow doors to be fully opened and not stick out past the edges of the body) A curbside forward entry door (with stepwell) also provided. Flooring of body to be aluminum diamond plate floor including (2) front corner drain holes (for washout/hoseout) Standard 040 aluminum roof. This proposal includes mounting &amp; installation of the van body to customer-supplied chassis. Exterior lighting to be all-LED, all-Whelen, and will include (6) scene lights, and (8) M9-series split red/blue lights. TriVan to install body. Customer to arrange pickup from Ferndale WA. Full AutoCad presentation drawings will be provided to Mat-Su Borough for approval prior to manufacturing the body.</p>

<b>Subtotal</b>
<b>Sales Tax (0.0%)</b>
<b>Total</b>



**TriVan Truck Body**

1385 West Smith Road  
Ferndale, WA 98248

Ph (360) 380-0773 www.trivan.com  
Fax (360) 312-1398

# Estimate

Date	Estimate #
7/23/2024	10258

Name / Address
Matanuska-Susitna Borough Brent Davenport 680 N. Seward Meridian Parkway Wasilla AK 99654

Ship To
FOB Ferndale WA

P.O. No.	Terms	Due Date	Rep	Account #	FOB	Project
TBD	Due on receipt	8/21/2025	Ryan		Ferndale WA	
Item	Description					
CHASSIS INFO	CHASSIS INFORMATION (CUSTOMER PROVIDED) 2023 Chevy 5500 Crew Cab 4x4, 120" cab-axle ~ GVWR: 19,500 lb Payload Plus Upgrade Package ~ dual rear wheels ~ 4-door crew cab ~ Mat-Su to arrange to have this chassis drop-shipped to TriVan Truck Body					
DIMENSIONS	DIMENSIONS: Length: 16'L(od) plus 4' over-cab extension Width: 8'W(od) Height: 7'H(id)					
DESIGN DRA...	DESIGN DRAWINGS: AutoCad design drawings shall be provided for Mat-Su approval prior to manufacture.					
SUBFRAME 2x2	SUBFRAME & WHEEL-WELLS: Subframe constructed of 2"x2" tubular steel cross-members 16" on center with longsills to suit supplied chassis. Includes wheel wells for low floor height. Includes custom clearance for tire chains.					
BUMPER-STEP	STEP BUMPER + FOLDOUT STEP + HITCH + ANCHOR POINTS: 10"D galvanized steel Grip Strut step bumper installed at rear. Includes tapered 45 degree corners ~ Bumper to incorporate a Class V receiver hitch that is reinforced to chassis frame rails. ~ Bumper is primed & painted black  FOLDOUT STEP: Supply & Install (1) 48"W hinged foldout step off rear bumper, same Grip Strut material as main bumper ~ foldout step to include a stainless) spring-loaded barrel bolt (to stow bumper securely in storage position)					
HITCH	CLASS V HITCH: Class V hitch receiver installed & reinforced to chassis frame rails. ~ Installation includes (1) 7-way ROUND COMMERCIAL trailer plug					
WALLS	WALL CONSTRUCTION: SnapLock wall construction. Note: all exterior doors to be FORMED style.					

<b>Subtotal</b>
<b>Sales Tax (0.0%)</b>
<b>Total</b>



**TriVan Truck Body**

1385 West Smith Road  
Ferndale, WA 98248

Ph (360) 380-0773 www.trivan.com  
Fax (360) 312-1398

# Estimate

Date	Estimate #
7/23/2024	10258

Name / Address
Matanuska-Susitna Borough Brent Davenport 680 N. Seward Meridian Parkway Wasilla AK 99654

Ship To
FOB Ferndale WA

P.O. No.	Terms	Due Date	Rep	Account #	FOB	Project
TBD	Due on receipt	8/21/2025	Ryan		Ferndale WA	
Item	Description					
SKIRTING	SKIRTING: Snap-Lock panel perimeter wall skirting flush to bottom of cab. ~ rounded wheel cutouts with rubber fender crowns ~ cutouts are large enough to allow tire-chain clearance.					
KICKOVER-4'	KICKOVER 4'L sloped kickover installed at front of body, finished & lined per rest of van body interior, ~ Insulated 3" urethane foam, lined in Kemlite over plywood. ~ includes an exterior wraparound continuous drip rail system ~ includes diamond plate protective wear plate on interior (near bottle storage rack)					
ROOF	ROOF: Standard .040" single piece aluminum roof, cross-bows 24" on center, with standard TriVan crown.					
WINDOWS	WINDOWS: No windows.					
ALUM DIAMO...	FLOORING Flooring of van body interior to be 3/16" aluminum diamond plate flooring. No bedliner.					
INSULATION	INSULATION 3" urethane spray-foam insulation (R21) applied to walls, ceiling, under floor and entry doors and kickover.					
LINING	WALL LINING: Walls & ceiling lined in white, aluminum sheeting on full interior, including 4" retainer lip installed on edge of kickover.					
FINISH TRIM &...	TRIMOUT Extra labor for interior lining on interior of specialty units (including extra trim work, capping, caulking, special cutouts)					
DOORS	REAR DOORS: (2) 25" formed aluminum double doors at rear (approx 50"W clear opening) with TriMark paddle handles, stainless piano hinges and cast aluminum holdbacks. Doors to be insulated and lined to match the body interior.					

<b>Subtotal</b>
<b>Sales Tax (0.0%)</b>
<b>Total</b>



**TriVan Truck Body**

1385 West Smith Road  
Ferndale, WA 98248

Ph (360) 380-0773 www.trivan.com  
Fax (360) 312-1398

# Estimate

Date	Estimate #
7/23/2024	10258

Name / Address
Matanuska-Susitna Borough Brent Davenport 680 N. Seward Meridian Parkway Wasilla AK 99654

Ship To
FOB Ferndale WA

P.O. No.	Terms	Due Date	Rep	Account #	FOB	Project
TBD	Due on receipt	8/21/2025	Ryan		Ferndale WA	

Item	Description
STEPWELL (2)	CURBSIDE DOOR: (1) 30"W x 84" Aluminum FORMED curbside door entry door, located at very front, with (2) recessed aluminum diamondplate inside steps. Includes TriMark paddle handle and cast aluminum holdback. Door is insulated & lined per rest of body interior.
INTERIOR FINI...	All-aluminum construction, painted white.  ROADSIDE INTERIOR FURNISHINGS: ~ Supply & install the following: ~ (3) aluminum J-style hanger hooks on front wall, as space allows ~ (2) 54"W x 22"D aluminum shelving units, each with (3) adjustable shelves ~ (1) 72"W x 22"D Formica work counter (between the 2 shelving units) with (2) lower drawers  CURBSIDE INTERIOR FURNISHINGS: Supply & Install the following: ~ (1) +/- 81"W x 22"D x 27"H cushioned high-density foam bench-seat cushion over top of storage box bench-seat. no back-rest. Cushion is to be wrapped in black marine-grade vinyl and bench ~ (1) +/- 32"W x 22"D x 84"H Floor-to-ceiling double-door cabinet at very rear of body (right-hand-side upon entry at rear doors); ~ Upper +/- 5'H of cabinet to be solid alum doors w/ adjustable shelves. ~ Lower +/- 2'H of cabinet has (2) 250lb extra tall lower drawers, with travel-safe latches (non-locking is ok) and rubber matt inserts ~ (1) 4-space x 12"H overhead cubby compartment cabinet (open-faced, with front retainer lip) directly above bench-seat (for personal gear)
SEATBELTS	SEATBELTS: deleted.
FUEL FILLER	FUEL FILLER & DEF FILLER: Supply & install recessed fuel filler pod on driver side of vehicle wheelhouse skirt panel area, with standard hose assembly, to suit chassis fuel tank and DEF tank as necessary.

<b>Subtotal</b>
<b>Sales Tax (0.0%)</b>
<b>Total</b>



**TriVan Truck Body**

1385 West Smith Road  
Ferndale, WA 98248

Ph (360) 380-0773 www.trivan.com  
Fax (360) 312-1398

# Estimate

Date	Estimate #
7/23/2024	10258

Name / Address
Matanuska-Susitna Borough Brent Davenport 680 N. Seward Meridian Parkway Wasilla AK 99654

Ship To
FOB Ferndale WA

P.O. No.	Terms	Due Date	Rep	Account #	FOB	Project
TBD	Due on receipt	8/21/2025	Ryan		Ferndale WA	

Item	Description
EXTERIOR CO...	<p><b>EXTERIOR STORAGE COMPARTMENTS:</b>            ~ Supply &amp; install 1/8" aluminum exterior storage compartments, complete with FORMED aluminum doors with TriMark paddle handles.            ~ These compartments are to be "thru-the-floor" style, extending from bottom of skirt, up through the floor, per drawings            ~ Horizontal compartments will be located above the rear axle, both sides of truck body.</p> <p><b>DOOR HARDWARE:</b>            ~ Door hardware to be stainless steel recessed paddle handles with 2-point rotary latches &amp; adjustable stryker bolts            ~ All doors hinged on stainless steel piano hinges.</p> <p><b>ROADSIDE COMPARTMENTS, starting from very front:</b>            ~ RSV1 - (1) tall vertical compartment, single door, approx 24"W x 38"H, very front (3 adj shelves)            ~ RSV2 - (1) vertical compartment, single door, approx 22-3/4"W x 38"H, ahead of rear axle (2 adj shelves)            ~ RSH - (1) horizontal, double-door compartment, approx 61"W x 14"H, over rear axle. (no shelves)            ~ RSV3 - (1) vertical compartment, single door, approx 35"W x 38"H, very rear. (2 adj. shelves)            As space allows, Mat-Su has requested (1) additional roadside exterior compartment approx 24"W with shelves.</p> <p><b>CURBSIDE COMPARTMENTS ~ DELETED</b></p> <p><b>NOTE:</b>            ~ Horizontal compartment door to include detachable retainer cables (or chains) that allow the door to form either a flat work surface (when opened) or to lay flat against the side of the body (with cables detached) All vertical exterior compartment doors will include gas struts (to hold doors open and assist in door closure)</p>
12V ELECTRI...	<p><b>FMVSS ELECTRICAL</b>            To TriVan standard wiring specifications including:            ~ All wiring joints to be soldered and heat-shrunk with insulated tubing.            ~ LED Signal Lights: 4" round stop-tail-turn signals            ~ LED Reverse Lights: 4" round stop-tail-turn signals            ~ LED licence plate light and reflectors as necessary.</p>

<b>Subtotal</b>
<b>Sales Tax (0.0%)</b>
<b>Total</b>



**TriVan Truck Body**

1385 West Smith Road  
Ferndale, WA 98248

Ph (360) 380-0773 www.trivan.com  
Fax (360) 312-1398

# Estimate

Date	Estimate #
7/23/2024	10258

Name / Address
Matanuska-Susitna Borough Brent Davenport 680 N. Seward Meridian Parkway Wasilla AK 99654

Ship To
FOB Ferndale WA

P.O. No.	Terms	Due Date	Rep	Account #	FOB	Project
TBD	Due on receipt	8/21/2025	Ryan		Ferndale WA	

Item	Description
12V LIGHTING...	<p><b>INTERIOR 12V LED LIGHTING:</b> Supply &amp; install (8) Maxxima M84418-SW LED surface-mounted interior cargo lights, installed on ceiling, 2 parallel runs of (4) lights, end-to-end evenly spaced, switched @ rear door. All lights on one switch.</p> <p>COMPARTMENT 12V LIGHTING: deleted.</p>
RED/BLUE LE...	<p><b>EMERGENCY LIGHTING PACKAGE:</b></p> <p><b>RED/BLUE FLASHERS:</b> Supply &amp; install (6) Whelen M9J "M" series super linear red/blue LED flasher lights (each with M9FC chrome flange): ~ (2) on rear wall, (2) on curbside, (2) on roadside, plus (2) Whelen LINZ6 red/blue in chassis grille. ~ Includes (1) illuminated switch in cab to activate all at once. (see LIGHT CONTROLS)</p> <p><b>LED SCENE LIGHTS:</b> Supply &amp; install (6) Whelen M9LZC "M" series LED scene lights (each with M9FC chrome flange) ~ (2) on rear wall, (2) on curbside, (2) on roadside ~ Includes (1) illuminated switch in cab (see LIGHT CONTROLS)</p> <p><b>LIGHT CONTROLS:</b> Supply &amp; install (1) switch controller console in cab to control red/blue flashers &amp; scene lights</p> <p><b>TOMAR:</b> Siren/amplifier and controls in cab, installed, as on previous unit. Note: the Whelen lightbar (on top of cab roof) is not part of this quotation.</p>

<b>Subtotal</b>
<b>Sales Tax (0.0%)</b>
<b>Total</b>



**TriVan Truck Body**

1385 West Smith Road  
Ferndale, WA 98248

Ph (360) 380-0773 www.trivan.com  
Fax (360) 312-1398

# Estimate

Date	Estimate #
7/23/2024	10258

Name / Address
Matanuska-Susitna Borough Brent Davenport 680 N. Seward Meridian Parkway Wasilla AK 99654

Ship To
FOB Ferndale WA

P.O. No.	Terms	Due Date	Rep	Account #	FOB	Project
TBD	Due on receipt	8/21/2025	Ryan		Ferndale WA	
Item	Description					
INVERTER-30...	<p><b>INVERTER:</b> Supply &amp; Install (1) Xantrex 3000WPure Sinewave Inverter with Built-In Charger. To be hard-wired to (3) interior GFCI 15A duplex plugs and (1) exterior GFCI plug (curbside exterior) ~ Installation includes a control panel (suggested model 809-0910) installed at roadside desk area. ~ Installation also includes Fuse Block and fuse to suit. with automatic charge function to allow charging from vehicle alternator as well as from inverter.</p> <p><b>BATTERIES:</b> Includes installation of (2) Group 31 deep cycle batteries on slide out tray in bottom of driver side compartment second front front.</p>					
GRABHANDLE...	GRAB HANDLES: Supply & install (3) firetruck style grab handles, each with end-stanchions and rubber grip insert.					
PAINT	<p><b>PAINT:</b> Body exterior (excluding roof) painted Chevrolet white to match F-550 cab. Exterior compartment interiors left mill-finish aluminum.</p>					
UNDERCOATI...	<p><b>UNDERCOATING:</b> Underside of body to be fully undercoated, including bottom exterior undersides of all exterior bins.</p>					
MOUNTING	<p><b>MOUNTING:</b> Body to be mounted by TriVan on customer supplied chassis, includes TriVan mudflaps and anti-sway brackets.</p>					
FINISHING	<p><b>FINISHING:</b> Extruded aluminum drip rails installed above all exterior cabinet doors. 1 full wraparound continous drip rail on front of kickover, including 4' side arms for water run off diversion. 1 pair of TriVan mudflaps installed, including anti-sway brackets. Reflectors as necessary &amp; grab handles where required.</p>					
DELIVERY	<p><b>DELIVERY:</b> FOB TriVan Truck Body Ferndale WA (we are approximately a 3 hour drive from the Span Alaska Barge terminal)</p>					
	<p>THIS QUOTATION EXPIRES 9/30/2024 Build time is approx 500 days after receipt of chassis.</p>					

<b>Subtotal</b>	USD 186,912.72
<b>Sales Tax (0.0%)</b>	USD 0.00
<b>Total</b>	USD 186,912.72

**From:** [Brent Davenport](#)  
**To:** [Talia Derner](#)  
**Subject:** FW: REVISED QUOTATION, Hazmat custom body, TriVan Truck Body  
**Date:** Wednesday, July 24, 2024 8:45:52 AM  
**Attachments:** [Mat-Su Borough - 16" Hazmat Van Body - Quotation for Brent Davenport - July 2024 v 4.0.pdf](#)

---

**From:** Ryan VanDriel <[rvandriel@trivan.com](mailto:rvandriel@trivan.com)>  
**Sent:** Tuesday, July 23, 2024 3:17 PM  
**To:** Brent Davenport <[Brent.Davenport@matsugov.us](mailto:Brent.Davenport@matsugov.us)>  
**Subject:** REVISED QUOTATION, Hazmat custom body, TriVan Truck Body

**[EXTERNAL EMAIL - CAUTION: Do not open unexpected attachments or links.]**

Good afternoon Brent,

On behalf of TriVan Truck Body, I'm very pleased to submit a quotation to you for the 16' customized aluminum insulated HAZMAT van body, per our conversation earlier today.

The current estimated build time is 500 days after receipt of customer provided chassis.

A 35% deposit is required at time of order, with full balance due after customer approval of completed truck and prior to pick up.

See attached quote. This quote is good for 60 days (expires September 30 24)

**Ryan Vandriel**  
**TriVan Truck Body**  
**1385 West Smith Road**  
**Ferndale, WA 98248**  
**Ph # 360-380-0773**  
**Cell # 360-815-7610**  
**Web [www.trivan.com](http://www.trivan.com)**  
**[Check us out on YOUTUBE!!](#)**

