


**SUBJECT:** Award of bid number 22-126B to Northern Asphalt Construction, Inc. for the contract amount of \$392,443.00 to improve Emswiler Drive and Sunday Drive.







**AGENDA OF:** May 3, 2022

**ASSEMBLY ACTION:**

*Approved Under the Consent  
Agenda 5-3-22* 

**MANAGER RECOMMENDATION:** Present to the Assembly for consideration.

**APPROVED BY MICHAEL BROWN, BOROUGH MANAGER:** 

Route To:	Department/Individual	Initials	Remarks
	Purchasing Officer		
	Public Works Director		
	Finance Director		
	Borough Attorney		
	Borough Clerk		

**ATTACHMENT (S) :** Fiscal Note: Yes X No         
 Analysis Sheet (1p)  
 Scope of Work (1p)

**SUMMARY STATEMENT:** On March 23, 2022, the Matanuska-Susitna Borough Purchasing Division issued a solicitation requesting bids from qualified contractors to upgrade and improve the drainage along 3,275 linear feet of Emswiler Drive and Sunday Drive. This project will involve, but is not limited to, clearing, grubbing, excavation, import and placement of borrow material, import and placement of aggregate base and surface courses, placing hot mix asphalt, installing drainage culverts and placing topsoil and seed. Construction Services purchased will support the Public Works Department in assembly district #7.

In response to the advertisement, three bids were received. Award recommendation is being made to Northern Asphalt Construction, Inc. as the lowest responsive and responsible bidder based on Total Bid Amount.

The substantial completion date for this project is September 30, 2022 with the final completion of December 16, 2022.

In accordance with MSB 3.08.170(B), Administration requests authority to modify the resulting contract completion date by 30 days for unforeseen circumstances.

The Public Works Department, Project Management Division will be administering the contract.

**RECOMMENDATION OF ADMINISTRATION:** Award of **BID NUMBER 22-126B** to **NORTHERN ASPHALT CONSTRUCTION, INC.** for the contract amount of **THREE HUNDRED NINETY-TWO THOUSAND FOUR HUNDRED FORTY-THREE DOLLARS AND 00/100 CENTS (\$392,443.00)** to **IMPROVE EMSWILER DRIVE AND SUNDAY DRIVE.**

MATANUSKA-SUSITNA BOROUGH  
FISCAL NOTE

Agenda Date: May 3, 2022

SUBJECT: Award of bid number 22-126B to Northern Asphalt Construction, Inc. for the contract amount of \$392,443.00 to improve Emswiler Drive and Sunday Drive.

ORIGINATOR: Purchasing

FISCAL ACTION (TO BE COMPLETED BY FINANCE)	FISCAL IMPACT <u>YES</u> NO
AMOUNT REQUESTED <u>\$392,443</u>	FUNDING SOURCE <u>RSA Capital Projects</u>
FROM ACCOUNT # <u>410.000.000 442.000</u>	PROJECT # <u>30042</u>
TO ACCOUNT :	PROJECT #
VERIFIED BY: <u>[Signature]</u>	CERTIFIED BY:
DATE: <u>4-22-22</u>	DATE:

EXPENDITURES/REVENUES:

(Thousands of Dollars)

OPERATING	FY2022	FY2023	FY2024	FY2025	FY2026	FY2027
Personnel Services						
Travel						
Contractual						
Supplies						
Equipment						
Land/Structures						
Grants, Claims						
Miscellaneous						
TOTAL OPERATING						

CAPITAL	<u>392.4</u>					
---------	--------------	--	--	--	--	--

REVENUE						
---------	--	--	--	--	--	--

FUNDING:

(Thousands of Dollars)

General Fund						
State/Federal Funds						
Other	<u>392.4</u>					
TOTAL	<u>392.4</u>					

POSITIONS:

Full-Time						
Part-Time						
Temporary						

ANALYSIS: (Attach a separate page if necessary)

PREPARED BY: \_\_\_\_\_ PHONE: \_\_\_\_\_  
 DEPARTMENT: Chesenne Hernal DATE: 4/25/2022  
 APPROVED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

# ~PRELIMINARY RESULTS~

## MATANUSKA-SUSITNA BOROUGH: PURCHASING BID OPENING ANALYSIS SHEET

22-126B Emswiler – Sunday – Road Improvements

BIDDER		Western Const. + Equip	Northern Asphalt	Granite Const. Co.
Signed Bid Form		<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
Receipt of Addendum - #1		<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
Bid Guarantee		<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
BID ITEM	DESCRIPTION	TOTAL BID AMOUNT	TOTAL BID AMOUNT	TOTAL BID AMOUNT
1.	Sum of all items as listed in the Bid Schedule	\$ 514,420.00	\$ 392,443.00	\$ 535,285.00

BIDDER				
Signed Bid Form		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Receipt of Addendum - #1		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Bid Guarantee		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
BID ITEM	DESCRIPTION	TOTAL BID AMOUNT	TOTAL BID AMOUNT	TOTAL BID AMOUNT
1.	Sum of all items as listed in the Bid Schedule	\$	\$	\$

**RECOMMENDATION:** ALL BIDS ARE TAKEN UNDER ADVISEMENT

Friday, April 15, 2022  
DATE



PURCHASING OFFICER



PURCHASING REPRESENTATIVE

PURCHASING REPRESENTATIVE

AM 22-039

PROJECT MANAGER

WITNESS

WITNESS

WITNESS



**BID #22-126B**  
**EMSWILER - SUNDAY - ROAD IMPROVEMENTS**  
**SCOPE OF WORK**

General

This project's purpose is to upgrade and improve the drainage along 3,275 linear feet of Emswiler Drive and Sunday Drive. This project will involve, but is not limited to, clearing, grubbing, excavation, import and placement of borrow material, import and placement of aggregate base and surface courses, placing hot mix asphalt, installing drainage culverts and placing topsoil and seed.

This project is located in Willow off W. Long Lake Road near milepost 69 of the Parks Highway. See project location and vicinity maps.

All construction shall be completed in accordance with the current Alaska Department of Transportation and Public Facilities (ADOT&PF) Standard Specifications for Highway Construction (SSHC) 2017 Edition. Project specific special provisions are provided in the following sections. The requirements contained in these specifications and special provisions are hereby made a part of this solicitation and resultant contract.

Work Description

- Supply labor, equipment, materials and supplies to perform the required work as shown on the construction plans for MSB project number 21-20-0906.
- Contractor is to provide resources to complete this project without any adjustments in the original bid amount or contract time.
- Contractor is required to obtain an ADEC APDES permit prior to utility relocation activities. Utility relocation work done by the utility companies will be performed under this permit.
- Contractor shall complete ROW and utility easement staking and clearing and all necessary SWPPP items for utility relocation support upon NTP. This work shall be included in items 201(3B), 642(1), 641(1), and 641(3). Additional stump removal for utility support will be directed if needed and is not included in these items. The anticipated additional utility support areas are as follows:
  - STA 10+00 to 14+00 LT
  - STA 15+50 to 25+60 LT
  - STA 26+15 to 37+00 LT
  - STA 37+00 to 37+20 RT
- Contractor shall coordinate the road improvements with all utility relocation work.
- Request locates from the utilities having facilities in the area. Use the Alaska Digline, Inc. Locate Call Center. See Section 105-1.06 for digline number and a list of utility companies in the area.
- Work Zone speed limit: Limit speed of vehicles associated with construction to 20 miles per hour within project limits.
- Normal work time will be between 7 a.m. and 7 p.m. Extensions will be considered and approved by the MSB Inspector.
- Time is of the essence. Work shall be completed in one continuous timeframe after utility relocations are completed. Substantial completion shall be achieved by September 30<sup>th</sup>, 2022. Final completion shall be achieved by December 16<sup>th</sup>, 2022.
- Estimated project magnitude is less than \$446,000.

Am 22-039